MONTICELLO RESERVOIR FISHERIES HABITAT ENHANCEMENT PLAN

PARR HYDROELECTRIC PROJECT

FERC No. 1894

Prepared for:

South Carolina Electric & Gas Company Cayce, South Carolina

Prepared by:

Kleinschmidt

Lexington, South Carolina www.KleinschmidtGroup.com

October 2017

MONTICELLO RESERVOIR FISHERIES HABITAT ENHANCEMENT PLAN

PARR HYDROELECTRIC PROJECT

FERC No. 1894

Prepared for:

South Carolina Electric & Gas Company Cayce, South Carolina

Prepared by:

Kleinschmidt

Lexington, South Carolina www.KleinschmidtGroup.com

October 2017

MONTICELLO RESERVOIR FISHERIES HABITAT ENHANCEMENT PLAN

PARR HYDROELECTRIC PROJECT FERC No. 1894

SOUTH CAROLINA ELECTRIC & GAS COMPANY

TABLE OF CONTENTS

1.0	INTRODUCTION				
2.0	MET	HODS		2	
3.0	RESU	JLTS		3	
	3.1	SPAW	NING HABITAT ENHANCEMENTS	3	
	3.2		ERY HABITAT ENHANCEMENTS		
	3.3 DEEP-WATER HABITAT ENHANCEMENT			6	
	3.4 Inst	INSTA	LLATION COSTS	8	
		3.4.1	STITUTE DED INTIERE COSTS		
			NURSERY HABITAT ENHANCEMENTS		
		3.4.3	DEEP-WATER HABITAT ENHANCEMENTS	9	
4.0	DISC	CUSSION	N	10	
5.0	PRO	ΓΕСΤΙΟ	N MITIGATION AND ENHANCEMENT MEASURES	10	
6.0	REFE	ERENCE	ES	11	

LIST OF TABLES

TABLE 1-1	MONTICELLO RESERVOIR MONTHLY AVERAGE ELEVATIONS: 2005-2013	.2
TABLE 3-1	SPAWNING HABITAT ENHANCEMENT COSTS	.8
TABLE 3-2	NURSERY HABITAT ENHANCEMENT COSTS	.9
TABLE 3-3	DEEP-WATER HABITAT ENHANCEMENT COSTS	.9

LIST OF FIGURES

FIGURE 3-1	COMMERCIALLY AVAILABLE 3-FOOT DIAMETER PLASTIC POOL	1
FIGURE 3-2	MOSSBACK SAFE-HAVEN KIT	5
FIGURE 3-3	MOSSBACK TROPHY TREE KIT	7
FIGURE 3-4	MOSSBACK TROPHY TREE XL KIT	7

LIST OF APPENDICES

- APPENDIX A MONTICELLO RESERVOIR FISH HABITAT ENHANCEMENT AREAS
- APPENDIX B MONTICELLO RESERVOIR FISH ESTIMATED HABITAT ENHANCEMENT COSTS

MONTICELLO RESERVOIR FISHERIES HABITAT ENHANCEMENT PLAN

PARR HYDROELECTRIC PROJECT FERC No. 1894

SOUTH CAROLINA ELECTRIC & GAS COMPANY

1.0 INTRODUCTION

South Carolina Electric & Gas Company (SCE&G) is the Licensee of the Parr Hydroelectric Project (FERC No. 1894) (Project). The Project consists of the Parr Shoals Development and the Fairfield Pumped Storage Development. Both developments are located along the Broad River in Fairfield and Newberry Counties, South Carolina.

The Project is currently involved in a relicensing process which involves cooperation between SCE&G, as licensee, and a variety of stakeholders including state and federal resource agencies, state and local government, non-governmental organizations (NGOs), and interested individuals. SCE&G established several Technical Working Committees (TWCs) comprised of interested stakeholders with the objective of identifying Project-related resource issues and impacts.

During issue scoping meetings, the Fisheries TWC identified the need for a Reservoir Fluctuation Study on the Parr and Monticello Reservoirs. The operating regime for the Project consists of a lowering and a refilling of the Project's two reservoirs on a daily basis. Monticello Reservoir is currently permitted to fluctuate up to 4.5 feet. However, the amount that the Project reservoirs fluctuate will vary dependent on load demands and system needs. The magnitude of daily fluctuations also varies seasonally in both impoundments, with the largest average daily fluctuations generally occurring in June, July, and August in both reservoirs (Table 1-1).

MONTHLY AVERAGE RES. ELEV.						
MAX MIN RANG						
Jan	423.92	422.32	1.60			
Feb	423.93	422.45	1.49			
Mar	423.82	422.18	1.66			
Apr	424.08	421.88	2.22			
May	424.42	421.64	2.80			
June	424.74	421.42	3.33			
Jul	424.69	421.38	3.29			
Aug	424.71	421.31	3.40			
Sep	424.53	421.45	3.06			
Oct	424.02	421.83	2.18			
Nov	423.61	422.00	1.61			
Dec	423.86	422.28	1.58			
AVERAGE	424.19	421.84	2.35			

TABLE 1-1MONTICELLO RESERVOIR MONTHLY AVERAGE ELEVATIONS: 2005-2013

During February through April, when many fish species are spawning in shallow water habitat, average daily fluctuations range from 1.6-2.4 feet in Monticello Reservoir (TWC Meeting presentation 12-19-13). Resource agencies and stakeholders expressed concerns that these daily and seasonal fluctuations may be affecting aquatic habitat along the shorelines of the reservoirs and fish spawning and recruitment.

2.0 METHODS

This study report was developed as a result of the Monticello Reservoir Fluctuation Study to assess the effects of fluctuations on reservoir habitat. The bases for this study can be found in the following documents: Fisheries TWC Meeting notes from April 2014, September 2015, March 2016, and May 2016, the Revised Reservoir Fluctuation Study Plan, and the Parr and Monticello Reservoir Fluctuation Study. The April 2014 TWC meeting identified the study objectives relative to each reservoir. It was decided that Monticello would be assessed qualitatively to identify areas that could be candidates for habitat enhancement. The September 2015 meeting identified potential habitat enhancement areas and the types of enhancements that would be explored: spawning, nursery, and deep-water. The subsequent March 2016 meeting involved discussions of the findings of the Reservoir Fluctuation Study and refining of the habitat enhancements for Monticello Reservoir. The group further refined the types of structures that

could be used for each enhancement and the amount of enhancement that could be provided to an identified area. The final TWC meeting in May 2016 involved a site visit to Monticello Reservoir to confirm the potential enhancement sites and the exact location and amount of enhancements that could be installed at a given site.

3.0 **RESULTS**

The TWC proposed potential fish habitat enhancements to be placed throughout Monticello Reservoir to mitigate for reservoir fluctuation impacts on current shoreline areas. Habitat enhancement structures would be installed to enhance spawning, nursery, and deep-water habitats available within Monticello Reservoir. The habitat enhancement structures would serve two purposes within the reservoir. First, the structures could provide enhanced fish production within the reservoir. Second, they would concentrate fish as an enhancement for recreational fishermen (Wagner 2016). Maps of the proposed locations within Monticello Reservoir for fish habitat enhancement are included in Appendix A. Descriptions for each proposed enhancement and total PM&E installation costs are presented in the following sections.

3.1 SPAWNING HABITAT ENHANCEMENTS

The proposed spawning habitat enhancements could be made by the installation of "spawning bed" structures. These structures would consist of commercially available three-foot diameter plastic pools (of varying color based upon vendor) (Figure 3-1) filled with 3-4 inches (in.) of pea gravel/sand. While the commercially available plastic pools were used for purposes of estimating costs and materials, the TWC suggested that other more permanent spawning structure materials may be considered. There were eight spawning areas identified by the TWC and spawning beds could be installed in each area identified for spawning habitat enhancement. The structures would be constructed on a pontoon style work boat and lowered into place via a three-point attachment rope system and winch. The enhancement locations would be located in areas that are approximately 5 to 6 feet deep when the reservoir is at full pool, leaving the spawning beds 0.5 to 1.5 feet underwater at the lowest reservoir elevation.



FIGURE 3-1 COMMERCIALLY AVAILABLE 3-FOOT DIAMETER PLASTIC POOL (Color may vary based upon vendor selected.)

Timing of Installation

Due to TWC concerns over the resilience of the proposed spawning structures, these habitat enhancements will be installed and evaluated in a stepwise approach. The proposed number of spawning structures to be installed during the new license is 360. Based on TWC recommendations, SCE&G will install 15 spawning beds in each of the 8 coves identified for spawning habitat enhancement (Appendix A) within the first three years of the new license. The SCDNR may request to vary the spawning structure material, substrate material, and/or substrate depth to evaluate fish preferences. SCE&G and SCDNR will develop a matrix to test the effects of these variables. The installed spawning beds will be inspected by SCE&G (underwater camera observation) after two spawning seasons for condition and evidence of use by fish. SCE&G will report observations to SCDNR and consult on the installation of up to 240 (30 structures per 8 locations) additional spawning beds to be installed over the following two years.

3.2 NURSERY HABITAT ENHANCEMENTS

Nursery habitat enhancements could be made by the installation of Mossback Safe-Haven structures. The safe-haven structures are made up of three 50 inches tall PVC posts, 72 50 inches long composite limbs, a three-post base, and a three-hole shade top (Mossback 2016) (Figure 3-2). The nursery structures would be constructed on a pontoon style work boat, weighted with a concrete cinder block, and lowered into position via rope. The structures would be installed at a depth sufficient to leave approximately four feet of water above the top of the structure at the lowest reservoir elevation. Three safe-haven structures would be installed at each point marked

by the TWC for nursery habitat enhancement (Appendix A). A total 111 nursery structures would be installed based on TWC recommendations.



FIGURE 3-2 MOSSBACK SAFE-HAVEN KIT

During the Fisheries TWC meeting on September 1, 2016, the SCDNR stated that they would like to investigate periodic "shoreline tree felling" in various areas around the reservoir as an aquatic habitat enhancement. Shoreline trees (including hardwood, pine or cedar trees) would be felled into the lake and cabled to the shoreline to insure they do not become a navigation hazard. SCE&G agreed to coordinate with the SCDNR on their efforts to introduce this aquatic habitat during the new license.

Timing of Installation

Within the first five years of the new license, SCE&G will install three Mossback Safe-Haven (or equivalent) structures for nursery habitat enhancements at each location identified in the Appendix A for a total of 111 structures. These nursery habitat enhancements will require no additional monitoring after installation.

3.3 DEEP-WATER HABITAT ENHANCEMENT

Deep-water habitat enhancements would be made by the installation of Mossback Trophy Tree and Trophy Tree XL structures. As an alternative, structures constructed by SCE&G could be used in place of the Mossback structures (TWC meeting March 2016). The Mossback Trophy Tree structure is made up of three 50 in. tall PVC posts, 36 50 in. long composite limbs, a threepost base, and a three-hole shade top (Mossback 2016) (Figure 3-3). The Mossback Trophy Tree XL structure is approximately eight feet tall and made up of six 50 in. tall PVC posts, with 72 50 in. long composite limbs, a three-post base, and a three-hole shade top (Mossback 2016) (Figure 3-4). The deep-water structures would be constructed on a pontoon style work boat, weighted with a concrete cinder block, and lowered into position via rope. The structures would be installed at a depth sufficient to leave 10-15 feet of water above the top of the structure at the lowest reservoir elevation. The TWC recommended that 15 deep-water enhancement structures would be installed at each location marked for enhancement (Appendix A). The structures would be positioned in a five by three grid around the enhancement area. If Mossback structures are used, the four corners of the grid would be Trophy Tree XL units with the regular Trophy Trees making up the final 11 units within the enhancement area. Each of these areas would be marked with a floating buoy for reference.

Timing of Installation

Within the first five years of the new license, SCE&G will install deep-water habitat enhancements and buoy markers at 13 sites identified by the TWC and presented in Appendix A. Each of these enhancements will consist of 11 Mossback Trophy Tree (or equivalent) structures (143 total) and 4 Mossback Trophy Tree XL (or equivalent) structures (52 total) for a total of 195 structures. These deep-water habitat enhancements will require no additional monitoring after installation.



FIGURE 3-3 MOSSBACK TROPHY TREE KIT



FIGURE 3-4 MOSSBACK TROPHY TREE XL KIT

3.4 INSTALLATION COSTS

Habitat enhancement implementation costs were evaluated to include the costs to purchase the enhancement structure materials and estimated installation costs. Cost evaluations were made using several assumptions. Those assumptions include:

- One work day is 20 man-hours (two people working 10 hours);
- the labor rate used is \$50/hour;
- installation of spawning beds would be 15 units/day;
- nursery habitat structures would be installed at a rate of 10 units/day; and
- deep-water habitat structures would be installed at a rate of 10 units/day.

Costs were evaluated for each individual enhancement structure and then grouped by enhancement type. Total costs for each habitat enhancement type are presented in the sections below. All estimates are based on 2016 prices for materials and labor. More detailed tables and information is presented in Appendix B.

3.4.1 SPAWNING BED MATERIAL COSTS

The cost of the materials for an individual spawning bed are approximately \$16 for the plastic pool, \$10.50 for the pea gravel/sand, and \$2 for the rope. Using these assumptions, we used a value of \$28.50 for the materials for each spawning bed. Installation costs were based on the previous stated assumptions. Total estimated cost including materials and installation for 360 spawning structures is \$34,260 (Table 3-1). This estimate does not include the cost of alternate spawning bed materials or the spawning structure evaluation and consultation with the SCDNR during the license.

TABLE 3-1 Spawning Habitat Enhancement Costs

SPAWNING HABITAT ENHANCEMENT					
Structure Costs	\$10,260.00				
Labor Costs	\$24,000.00				
TOTAL COSTS	\$34,260.00				

3.4.2 NURSERY HABITAT ENHANCEMENTS

The cost for materials for an individual Mossback Safe-Haven unit is \$209.99. This includes a discount for bulk orders. Installation costs were based on the previous stated assumptions. Total estimated cost for installation of 111 Safe-Haven structures is \$34,409.89 (Table 3-2).

 TABLE 3-2
 NURSERY HABITAT ENHANCEMENT COSTS

NURSERY HABITAT ENHANCEMENT					
Structure Costs	\$23,308.89				
Labor Costs	\$11,100.00				
TOTAL COSTS	\$34,408.89				

3.4.3 DEEP-WATER HABITAT ENHANCEMENTS

The cost for materials for an individual Mossback Trophy Tree is \$179 and for an individual Trophy Tree XL is \$359. This includes a discount for bulk orders. Installation costs were based on the previous stated assumptions. Total estimated cost for materials and installation is \$66,365.00. We did not include the price option for SCE&G to construct deep-water structures from recycled materials, but installation costs should be similar. This includes installation of one buoy (\$200) per site. We did not include a cost for periodic replacement of the buoys during the new license.

NURSERY HABITAT ENHANCEMENT					
Structure Costs	\$46,865.00				
Labor Costs	\$19,500.00				
TOTAL COSTS	\$66,365.00				

 TABLE 3-3
 DEEP-WATER HABITAT ENHANCEMENT COSTS

4.0 **DISCUSSION**

The TWC recommended aquatic habitat enhancements for Monticello Reservoir that should enhance fish production and recreational fishing on the reservoir. The total costs of implementing these habitat enhancements (based on 2016 costs) is approximately \$135,000 (Appendix B). These enhancements were proposed to offset the impacts of daily reservoir fluctuations and should create spawning and nursery habitat for juvenile fish that is not impacted by the maximum fluctuations. The placement of deep-water enhancements should also improve recreational fishing on the reservoir. Finally, implementation of this enhancement program should help to offset potential entrainment issues related to the operation of the Fairfield Development. Habitat structures have been located further up the lake away from the turbine intakes. Therefore, fish production and survival should be increased in the upper portions of the lake and these fish would be much less susceptible to entrainment by project operations.

5.0 PROTECTION MITIGATION AND ENHANCEMENT MEASURES

SCE&G proposes to provide these fish habitat enhancements on Monticello Reservoir as a Protection, Mitigation, and Enhancement (PME) measure for the renewal of the Parr Hydroelectric Project License.

Installation of both Nursery and Deepwater habitat enhancements are fairly straightforward.

- Within the first five years of the new license, SCE&G will install three Mossback Safe-Haven (or equivalent) structures for nursery habitat enhancements at each location identified in Appendix A of this report - for a total of 111 structures. These nursery habitat enhancements will not be monitored.
- Within the first five years of the new license, SCE&G will install deep-water habitat enhancements and buoy markers at 13 sites identified in Appendix A of this report. Each of these enhancements will consist of 11 Mossback Trophy Tree (or equivalent) structures (143 total) and 4 Mossback Trophy Tree XL (or equivalent) structures (52 total) for a total of 195 structures. These deep-water habitat enhancements will not be monitored.

Installation of the spawning structures will be performed in an adaptive management approach. TWC members expressed concern that the plastic pools might not be resilient or be used by target fish species. Therefore, SCE&G will install these habitat enhancements in a stepwise approach. Within the first three years of the new license, SCE&G will install 15 spawning beds as described in this report in each of the 8 coves (120 structures total) identified for spawning habitat enhancement as depicted in Appendix A of this report. The SCDNR noted during TWC discussions that they may request an alternate spawning bed material and that a variety of spawning substrate materials (pea gravel/sand) of various sizes and/or depth of substrates within the spawning structure may be evaluated on these initial installations. SCE&G and SCDNR will consult to develop a test matrix to evaluate the effects of these and other variables on the preference of fish to use the structure for spawning. The installed spawning seasons for the condition of the structure and evidence of use for fish spawning. SCE&G will report observations to SCDNR and consult on the installation of up to 240 (30 structures per 8 locations) additional spawning beds to be installed over the following two years after completion of consultation. All installed structures will be fitted with labels that include owner information. Signage will be installed at each public boat ramp informing the public that a habitat enhancement program is underway and not to disturb the structures if they encounter them.

6.0 **REFERENCES**

- Kleinschmidt. 2013. *Baseline Fisheries Resources Report: Parr Hydroelectric Project*. Prepared for SCE&G by Kleinschmidt Associates, Lexington, SC. November 2013.
- Kleinschmidt. 2016. *Parr and Monticello Reservoir Fluctuation Study*. Prepared for SCE&G by Kleinschmidt Associates, Lexington, SC. February 2016.

Mossback Fish Habitat. www.mossbackrack.com. Web. January 2016.

Wagner, Eric. "Review of Fish Habitat Improvement Methods for Freshwater Reservoirs." *Utah Division of Wildlife Resources*. N.p., n.d. Web. Apr. 2016.

APPENDIX A

MONTICELLO RESERVOIR FISH HABITAT ENHANCEMENT AREAS




Source: Kleinschmidt, Orbis, SCE&G



Source: Kleinschmidt, Orbis, SCE&G


- Nursery Habitat (3 units)
- Deepwater Fish Attractor (15 units)
- Spawning Habitat Enhancement Area

Deepwater enhancements will supplement existing fish attractor.



_egend

- Nursery Habitat (3 units)
- Deepwater Fish Attractor (15 units)
- Spawning Habitat Enhancement Area



- Nursery Habitat (3 units)
- Deepwater Fish Attractor (15 units)
- Spawning Habitat Enhancement Area

Site 4 -81.305772, 34.37<u>1733</u>

Feet 200

Scale: AS SHOWN	SCE&G
Project No:	COLUMBIA, SC
0455097.01	PARR HYDROELECTRIC PROJECT
Filename:	FERC PROJECT NO. 1894
see margin	MONTICELLO RESERVOIR
Drawn By: JJJ	HABITAT ENHANCEMENTS
JJJ Date Drawn:	204 Caughman Farm Ln., Suite 301 Lexington, SC 29072 Telephone: (803) 462-5620
10/7/2016	Fax: (803) 462-5619 www.KleinschmidtGroup.com

Source: Kleinschmidt, Orbis, SCE&G

100

50

0



Deepwater Fish Attractor (15 units)

Spawning Habitat Enhancement Area

Site 5 -81.327358, 34.36236

ß
Ê
2.1
Ħ
ements.mxd
em
õ
ar
-P
Enhanc
g
Ľ.
∢
llo
nticello Area 5
.Э
Ē
4
4
es
n.
<u>5</u> 0
Ξ
luctuation F
Ξ
131
Ę
Ĕ
щ
oir
0
E.
eser
Re
~
ŝ
4
\p[e]
fie
air
Щ,
arrF
Pa
3
ž
CE&
Ü
Š
uta
Oat
P,
ъ
ient
Client
Client
コ
-
-
コ

Scale: AS SHOWN	SCE&G
Project No:	COLUMBIA, SC
0455097.01	PARR HYDROELECTRIC PROJECT
Filename:	FERC PROJECT NO. 1894
see margin	MONTICELLO RESERVOIR
Drawn By: .I.I.J	HABITAT ENHANCEMENTS
111	204 Caughman Farm Ln., Suite 301
Date Drawn:	Kleinschmidt Lexington, SC 29072 Telephone: (803) 462-5620
10/7/2016	Fax: (803) 462-5619 www.KleinschmidtGroup.com

N

Source: Kleinschmidt, Orbis, SCE&G

75

0

150

Feet

300

- Nursery Habitat (3 units)
- Deepwater Fish Attractor (15 units)
- Spawning Habitat Enhancement Area

1000			1.	
		Site 6		at the set
•	3-	31.302466, 34.36		
12 A 38			an a the	a Aper
Steller The		1 wete	e da	
	家族な学	1. the	C. WAR	A A A
	- in	Star -	A Cal	the case
12-7	47.3	and the second s	· A BAR	ALL AND ALL
at the	A.	ALC MALLON	A state	ASS CONTRACT
			and the property of	271/00 14
Chi.	\$ /*	6 - A	Alar	as the first
	different a		Scale: AS SHOWN Project No:	SCE&G COLUMBIA, SC
A THE REAL	A RAN		0455097.01	PARR HYDROELECTRIC PROJECT
	12 3 X. 18	and the second	Filename: see margin	FERC PROJECT NO. 1894 MONTICELLO RESERVOIR
2013年2月2日的AL	A SARA		Drawn By: JJJ	HABITAT ENHANCEMENTS 104 Caughman Farm Ln., Suit Lexington, SC 20072 Falephone: (803) 462-5610 Falephone: (803) 462-5610 Www.KleinschmidtGroup.com
50 100	Feet 200	No. 19 States	Date Drawn:	204 Caughman Farm Ln., Suit Kleinschmidt Telephone: (803) 462-5620

Nursery Habitat (3 units) Δ

Deepwater Fish Attractor (15 units)

Spawning Habitat Enhancement Area

Path: G:_Client_Data\SCE&G\ParrFairfield_MXD\Reservoir Fluctuation Figures\Monticello Area 7 Enhancements.mxd

0



N

Nursery Habitat (3 units)

Deepwater Fish Attractor (15 units)

Spawning Habitat Enhancement Area

Deepwater enhancements will supplement existing fish attractor.



Ν



Nursery Habitat (3 units)

Deepwater Fish Attractor(15 units)





Source: Kleinschmidt, Orbis, SCE&G



Nursery Habitat (3 units)

Deepwater Fish Attractor (15 units)


Spawning Habitat Enhancement Area

Site 11 -81.333266, 34.33655

ALL CLARGE

0

	12 9	ALL MARK	a characteries	A 1 4743	
S. C.	State and		公外 第二章	A sale is	12 22
A REAL		The second		A LANS	8. 3. T
		A Real of	ALT MARTIN		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
	1510.4		ENTERSON P		
				Scale: AS SHOWN	SCE&G
		ALL CAL		Project No:	COLUMBIA, SC
Carl Land	AR PERE	6 1 8 1 8 1 8		0455097.01	PARR HYDROELECTRIC PROJECT
	· · · · · · · · · · · · · · · · · · ·	Contraction of the second		Filename:	FERC PROJECT NO. 1894
a marine	Contraction of the	1 41 4 1 M		see margin	MONTICELLO RESERVOIR
		_		Drawn By: JJJ	HABITAT ENHANCEMENTS
		Feet 🥂 🐜			204 Caughman Farm Ln., Suite 301 Lexington, SC 29072
150	300	600		Date Drawn:	Kleinschmidt Fax: (803) 462-5620
State of the	CERTER SERVICE	Section Section		10/7/2016	www.KleinschmidtGroup.com
e: Kleinschmid	t, Orbis, SCE&G				



Source: Kleinschmidt, Orbis, SCE&G

Sec.2

in the second

N AN ANAL

Nursery Habitat (3 units)

Deepwater Fish Attractor (15 units)

Spawning Habitat Enhancement Area

Spawning Habitat E	Enhancement Area		and the second second
			1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
			a construction of the
AN HARD			
		A second second	AND FLOOR
	Site 13		
	-81.28837, 34.3134	46	
			and the second se
1 day			
	- State State		10 A 127
PATER AND AND A	and the second	A Martin	
Astronom Frank	A KIN C		de Fr
	A STREET		La Start Che
	and the state of a	Service Providence	
	Stor and		All Street of
19 2 1 2 A	States and		
件制 "我们们有	the states we		
THE REAL PROPERTY		Scale: AS SHOWN Project No:	SCE&G COLUMBIA, SC
y was to	Sector and	0455097.01	PARR HYDROELECTRIC PROJEC
		Filename: see margin	FERC PROJECT NO. 1894 MONTICELLO RESERVOIR
	Feet	Drawn By:	HABITAT ENHANCEMENTS
100 200	400	Date Drawn: 10/7/2016	204 Caughman Farm Ln., Sui Lexington, SC 29072 Kleinschmidt Fax: (803) 462-5620 Fax: (803) 462-5619 www.KleinschmidtGroup.com

APPENDIX B

MONTICELLO RESERVOIR FISH HABITAT ESTIMATED ENHANCEMENT COSTS


Monticello Reservoir Fish Habitat Enhancements Costs for Materials and for Installation						
Enhancement Structure	Enhancement Locations	Structures per Enhancement Area	Total Structures	Costs per Structure	Total Structure Costs	
Spawning Bed	8	15	360	\$28.50	\$10,260.00	
Safe Haven	37	3	111	\$209.99	\$23,308.89	
Trophy Tree	13	11	143	\$179.00	\$25,597.00	
Trophy Tree XL	13	4	52	\$359.00	\$18,668.00	
Buoy Markers	13	1	13	\$200.00	\$2,600.00	
Total					\$80,433.89	
	·	•	•			•
Labor Costs	Hours/day	\$/hr	\$/day		Installation Assumptions	
Person 1	10	\$50	\$500		Day = 20 man-hours	
Person 2	10	\$50	\$500		10 nursery structures/day	
Total	20	\$50	\$1,000		10 deep-water structures/day	
	·	•	·	-	15 spawning structures	per day
Enhancement Type	Total Structure Costs	Install Speed (structure/day)	Install Days	Labor Costs (\$/day)	Total Labor Costs	Total PM&E (
Spawning Enhancement	\$10,260.00	15	24.0	\$1,000	\$24,000.00	\$34,2
Nursery Enhancement	\$23,308.89	10	11.1	\$1,000	\$11,100.00	\$34,4
Deep-water Enhancement	\$46,865.00	10	19.5	\$1,000	\$19,500.00	\$66,3
			1			i

\$80,433.89

Total

June 30, 2016

Note that these prices are valid for 2016 only and do not include a CPI for future costs.



E Costs ,260.00 408.89 \$66,365.00 \$135,033.89

\$54,600.00